

00011 ADVERTISEMENT FOR BIDS

Project No.: 23WL000001(514), 23ST000003(515), 23ST000005(516)

Owner: CITY OF NEWTON, KANSAS

Address: 201 E. 6th Street, P.O. Box 426
Newton, Kansas 67114

Separate sealed BIDS for the construction of: INTERIOR WATER LINE IMPROVEMENTS, INTERSECTION OF SE 10TH & SE 14TH ST CONNECTOR IMPROVEMENTS & PAVING-SWS IMPROVEMENTS TO SERVE FOX RIDGE ADDITION – PHASE 1.

will be received by City of Newton, Kansas

at the office of City Engineer, 201 E. 6th Street - 3rd Floor, Newton, Kansas 67114

until 11:00 AM (Local Time) Thursday, December 21, 2023, and then at said office publicly opened and read aloud.

The CONTRACT DOCUMENTS may be examined at the following locations:

City of Newton (316-284-6020), Kansas, 201 E. 6th, Newton, Kansas 67114

Copies of the CONTRACT DOCUMENTS may be obtained at:

Garver

located at 1995 Midfield Rd., Wichita, KS 67209

Standard Construction Specifications for Paving and Drainage Projects dated October 2017 may be purchased separately for \$10.00 each (non-refundable).

Contract documents will be held by the office of the City Engineer. The City Engineer will furnish one electronic copy of the project documents based on request. No paper copies will be furnished

The Owner reserves the right to waive any informalities or to reject any or all bids. No Bidder may withdraw his bid within 60 days after the actual date of the opening thereof.



Director of Public Works/City Engineer

11-30-23

Date

4. BIDDER shall complete the Work for the following price(s):

Group A-Interior Water Line Improvements

Item No.	Description	Quantity	Unit	Unit Price	Extension
1	8" PVC Pipe	6342	LF		
2	8" DI CL Pipe	12	LF		
3	8" Fire Hydrant Ass'y	13	EA		
4	2" Blowoff Assembly	1	EA		
5	8" MJ Gate Valve	19	EA		
6	Remove & Replace Split Rail Fence	150	LF		
7	Remove Existing 4" Waterline	95	LF		
8	Sand Backfill, Flush & Vibrate	480	LF		
9	Connect to Existing 6" Pipe	1	EA		
10	Maintain BMP's	1	LS		
11	Site Clearing	1	LS		
12	Site Restoration	1	LS		
13	Contractor Provided Testing	1	LS		
14	Seeding, Temporary	1	LS		
15	SWPPP Maintenance, Inspection & Reports	1	LS		
			Group A Subtotal		

Group B-Intersection of SE 10th St & SE 14th Connector Improvements

Item No.	Description	Quantity	Unit	Unit Price	Extension
1	Sawcut	718	LF		
2	Excavation	60	CY		
3	Fill, Compacted (95% Density)	1,742	CY		
4	AC Pavement 6" (4" Bit Base)	1,302	SY		
5	Crushed Rock Base 5", Reinforced	1,382	SY		
6	Subgrade Manipulation	1,382	SY		
7	Signing/Pavement Marking	1	LS		
8	Install Ditch Check	5	EA		
9	Maintain Existing BMPs	1	LS		
10	Seeding	1	LS		
11	Site Clearing	1	LS		
12	Site Restoration	1	LS		
13	Contractor Provided Testing	1	LS		
14	SWPPP Maintenance, Inspection & Reports	1	LS		
			Group B Subtotal		

Group C-Paving-SWS Improvement

Item No.	Description	Quantity	Unit	Unit Price	Extension
1	Sawcut	26	LF		
2	Excavation	40,831	CY		
3	Fill, Compacted (95% Density)	38,596	CY		
4	AC Pavement 6" (4" Bit Base)	19,554	SY		
5	Concrete Pavement (VG) 7" (Reinf)	1,085	SY		
6	Crushed Rock Base 6", Reinforced	24,985	SY		
7	Subgrade Manipulation	24,985	SY		
8	Concrete Curb, Full Height (6" & 1-1/2")	11,825	LF		
9	Concrete Curb, Mono Edge (6" & 1-1/2")	657	LF		
10	Concrete Sidewalk 6"	57,688	SF		
11	Wheelchair Ramp w/ Detectable Warnings	27	EA		
12	Inlet Hookup (Type 1A)	8	EA		
13	Inlet Hookup (Driveway)	9	EA		
14	Inlet Underdrain	325	LF		
15	Signing	1	LS		
16	Testing 95% Compaction Lots	1	LS		
17	12" RCP	439	LF		
18	15" Steel Casing Pipe	29	LF		
19	15" RCP	749	LF		
20	18" Steel Casing Pipe	37	LF		
21	18" RCP	663	LF		
22	24" RCP	1,299	LF		
23	30" RCP	35	LF		
24	36" RCP	787	LF		
25	42" RCP	183	LF		
26	Backyard Inlet (4' Dia)	7	EA		
27	Backyard Inlet (5' Dia)	4	EA		
28	Type 1A Inlet (5x3)	1	EA		
29	Type 1A Inlet (10x3)	3	EA		
30	Type 1A Inlet (10x5)	1	EA		
31	Type 1A Inlet (10x6)	1	EA		
32	Grated Driveway Inlet (Double)	6	EA		
33	Grated Driveway Inlet (Single)	1	EA		
34	Type A Manhole (5' Dia.)	2	EA		
35	Parking Area Striping/Marking	0	LS		
36	Light Stone Rip Rap	86	SY		
37	Sand Backfill, Jet, Vibrate	541	LF		
38	Install Curb Inlet Protection	14	EA		
39	Install Drop Inlet Protection	10	EA		
40	Install Silt Fence	759	EA		

Group C-Paving-SWS Improvement (Cont.)

Item No.	Description	Quantity	Unit	Unit Price	Extension
41	Install Back of Curb Protection	11,907	EA		
42	Install Construction Safety Fence (4')	1,457	EA		
43	Maintain Existing BMPs	1	LS		
44	Seeding (Temp)	1	LS		
45	Site Clearing	1	LS		
46	Site Restoration	1	LS		
47	Contractor Provided Testing	1	LS		
48	SWPPP Maintenance, Inspection & Reports	1	LS		
			Group C Subtotal		

(Add Alternate-Concrete Weir Improvements)

Item No.	Description	Quantity	Unit	Unit Price	Extension
1	Excavation	78	CY		
2	Fill, Compacted (95% Density)	62	CY		
3	8" PVC	33	LF		
4	Heavy Stone Rip Rap	112	SY		
5	Concrete Weir	1	LS		
			Add Alternate Subtotal		

INTERIOR WATER LINE IMPROVEMENTS, INTERSECTION OF SE 10TH & SE 14TH ST CONNECTOR IMPROVEMENTS & PAVING-SWS IMPROVEMENTS TO SERVE FOX RIDGE ADDITION – PHASE 1

TOTAL BID (A + B + C): \$ _____

(In Words) _____

Quantities are not guaranteed. Final payment will be based on actual quantities unless specified otherwise in Section 01150 of the Construction Specifications.

5. BIDDER agrees that the Work:

Will be substantially completed within 100 Working Days after the date when the Contract Time commences to run as determined below, and completed and ready for final payment within 110 Working Days after the date when the Contract Time commences to run.

BIDDER must choose a start date that is no later than February 12, 2024. The Contract Time will commence to run on this date. Contract must be signed/approved prior to start date.